

FIXTURES & FITTINGS

Lot 73 Te Mania Development

Date 16/05/2025



Job Number TA0463
Plan Version Date 27/02/2025
Plan Version Number P01
Client Name TBA
Site Address Lot 73
Te Mania
Te Puke

Please Note - All Information and Specification Detailed in the Contract Specification, Takes Precedence Over the Plans and Supersedes All Previous Written and/or Verbal Representations (Both Made or Implied) with Regards to Construction Materials, Fixtures and Inclusions in this Contract. Contract Pricing and Costings are Based on this Contract Specification.

GENERAL

Guarantees:	10 Year Standard (Defects & Maintenance) Master Build Guarantee (Loss Of Deposit and Non Completion Cover Included).
Insurance:	Builders All Risk and Public Liability
Plans:	Full Working Drawings Included. Plans and Design are Copywrite and Remain the Property of Mike Greer Homes Ltd No allowance for Home Star 6 processing or application
Noise Attenuation:	No Allowance for an Acoustic Report. If an Acoustic Report is Required this will be Charged as a Variation to the Customer, along with any Additional Work Required as a Result of the Report
Surveying:	Site Levels, Boundary Location Offset Pegs and Building Location Certificate Included. Any Other Necessary Fees are Not Included
Building Consent:	Building Consent Included as a Provisional Sum \$13800.00 Incl GST. No Allowance for Development Contributions. All Other Fees Including Subdivision Fees, Dept of Building & Housing Levies, Reserve Contributions and Resource Consents are Not Included and to be Treated as a Variation to Customer
Engineering:	Geotechnical Information and Soil Testing: Soil Report Included as a Provisional Sum \$1725.00 Site specific Geotech report not included. Should a Further Report be Required, this will Incur an Additional Cost, as will any Findings made by the Engineer Structural - Floor Slab/Floor Structure: Foundation/Slab Engineering included. Provisional Sum \$1725.00 incl GST Structural above Floor Slab/Flooring Structure: Not Included in Contract. Should an Engineers Design be Required, this will Incur an Additional Cost, as will any Findings made by the Engineer

Any Additional Requirements by the Engineer (Including the Design, Materials and Labour) will be a Variation to the Contract

SITE SERVICES

Water:	20mm Mains Supply Connected at Boundary. Work Outside Net Site Area not Included. 10 l/m from Dwelling Allowed for
Drains:	Sewer connected at Boundary, Stormwater connected at boundary via Detention Tank. Work Outside Net Site Area Not Included. 10 l/m from the Dwelling Allowed for. Provisional Sum \$21850.00 incl GST Please Note: Landscaping Drainage is Not included in the Contract (Unless Otherwise Stated under 'Landscaping' Section of Fixtures & Fittings)
Power:	16mm Neutral Screen Connected at Boundary. Work Outside Net Site Area not Included. Connection Fees not Included if Applicable. 10 l/m from the Dwelling Allowed for Temporary Site Power Included in Contract
Phone:	Underground 2 Pair Line Connected at Boundary (Connection to Network not Included) Work Outside Net Site Area not Included. 10 l/m from the Dwelling Allowed for.
Gas:	No allowance for gas.

SITE WORKS

Site Works:	A Site Scrape or Excavation to the House Area Only is Included in Foundation Provisional Sum. No Other Site Works are Included in this Contract which is Based on a Level and Easily Accessible Site No allowance for removal or disposal of contaminated fill. Clean fill allowed only. If testing and removal is required this will be treated as a variation to the contract
--------------------	---

In the Event Mike Greer Homes is Notified or Otherwise is Placed on Notice that the Site is Subject to the Historic Places Act or Otherwise Subject the Protection of Archaeological Sites, any Incurred Costs are Excluded from the Contract Price and would be Treated as a Variation to Contract.

STRUCTURE

Foundation:	Waffle Floor Slab. Excavate to 400mm & Backfill with compacted hardfill to maximum 1.0m Outside the Foundation Perimeter. FFL 250mm above Existing Ground Level. Provisional Sum \$35678.75 Incl GST.
Framing:	90 x 45mm Kiln Dried Pine & Treated as per NZBC. 2400mm Ceiling Height
Trusses:	Kiln Dried Pine or NZO and Treated as per NZBC and Manufacturers Specific Design
Ceiling Battens:	35mm Metal ceiling battens @ 600mm centres (Clipped)
Structural Steel:	Not Included - Will be a Variation if Required

INTERIOR WALL LININGS AND INSULATION

Insulation:		R2.6 Wall Batts to Exterior Walls. 2 x Layers R3.6 Ceiling Batts.
Internal Lining:	Main Linings:	Standard 10mm Plasterboard Lining to Walls and 13mm Plasterboard Lining to Ceilings
	Bathroom and Ensuite:	10mm Water Resistant Plasterboard Lining to Walls and 13mm Water Resistant Plasterboard Lining to Ceilings to All Wet Areas
Plasterboard Stopping:		Level 4 Paint Finish, with 55mm Cove to All Walls Excluding the Garage and Storage Cupboards Please Advise your Project Manager if you Choose a Dark Paint Colour as a Level 5 Stopping Finish may be Required. This will Require a Signed Variation to the Contract.
Plasterboard External Corners:		Square Stop
Painting:		Ceilings - Flat Finish. Walls and Exterior - Low Sheen Finish. Doors, Reveals, Bathrooms - Satin Enamel Finish. 4 Colours from a White Base Only. Picking Out of Skirtings or Any Trim in a Separate Colour is Additional to the Contract
Interior Design:		Exterior and Interior Colour Consultation Included

EXTERIOR

Roofing:	Down Pipes	Selected Colour and Size PVC Downpipes
	Fascia and Gutter:	Selected Colour Fascia and Quad Gutter
	Roof:	Selected Colour Longrun Corrugate
	Flashings:	Selected Colour Flashings to Match Roofing
Soffit Linings:		Hardiflex 4.5mm
Cladding:	Main Cladding:	James Hardie 150mm Oblique Board - Paint Finished (Single Colour Only, Picked out Trims Not included)
	Feature Claddings:	Cedar Weatherboards -J56 Profile - Stain Finished
Exterior Windows and Doors:		Aeonox Scratch-Resistant Powder Coated Aluminium, Double Glazed (Including Garage), Colour Matched Hardware. Stipolite Glass to Bathrooms, Ensuites and WC's
Entry Door:		Parkwood Aluminium Entry Door CFL Thermtek
Garage Door:		Dominator Range (Milano / Futura / Valero / Montana) Door & Opener with Two Remotes

FIXTURES & FITTINGS
Lot 73 Te Mania Development
Date 16/05/2025



INTERIOR

Doors:	1980 High Flush Panel MDF (Therma Door to Garage)
Wardrobe Doors:	MDF Flush Infill Sliders
Reveals:	40 x 10 Eco Pine Architraves to All Windows & Doors
Hardware:	Miles Nelson Range Lever Sets (2 Privacy), Kanso Lever Handle (Front Door), Miles Nelson Range Door Stops
Kitchen:	Kitchen Indicative of Floor Plan - Provisional Sum \$13800.00 incl GST
Skirting:	Bevelled Edge 60 x 10 Eco Pine
Shelving:	Melamine or Ventilated Shelving to Wardrobes and Linen Cupboards. Provisional Sum \$2300.00 incl GST

ELECTRICAL

Lighting and Plugs:	Mike Greer Homes Standard Electrical Schedule
Oven:	Samsung 60cm Stainless Steel 76L Wall Oven - NV7B41201AS/SA
Hob:	Samsung 60cm Ceramic Cooktop - CTR164NC01/XSA
Dishwasher:	Samsung Stainless Steel Dishwasher - DW60M6055FS
Rangehood:	Robinhood Stainless Steel 70cm Powerpack - RPC3CL70SS/MB
Waste Disposal:	Refer to Plumbing Schedule
Bathroom:	All Electrical Products Including Towel Rails, Heaters and Fans are Included in the Mike Greer Homes Standard Electrical Schedule
Exterior Electrical:	Included in the Electrical Schedule
Heating:	Fujitsu ASTH22KNTA Wall Mount Heatpump 6.5KW

PLUMBING

Laundry:	Aquatica Laundry Tub
Tapware:	Ion Chrome Kitchen Mixer
Hot Water:	Rheem 300 Litre 3kW Mains Pressure Cylinder

KITCHEN:

Kitchen:	Ion Chrome Kitchen Mixer
Fridge:	Plumbing Connection to Fridge Allowed
Waste Disposal:	Applico 1/2 HP GAWD12 Waste Disposal with Air Switch

BATHROOM:

Vanity:	NewTech 1200mm Double Basin Eva Two Drawer Vanity
Mirror:	Polished Edge. Measured to Fit Vanities x 750mm High
Shower:	1m x 1m (2-Walled) Flat Wall Lining, Low-Profile Acrylic Tray, Frameless Safety Glass Door, Easy Clean Waste. One Glass Shelf Included
Toilet:	Ion Back to Wall Toilet Suite with Soft Close Seat and Cover
Toilet Roll Holder:	Teka Chrome Toilet Roll Holder
Tapware:	Ion Chrome Shower Mixer, Ion Chrome Basin Mixer (2 No.) and Splash Plus Chrome 3F Slide Shower

EXTERIOR PLUMBING:

Exterior Plumbing:	3 x Exterior Taps
---------------------------	-------------------

WALL TILES

Wall Tile:	One Row 200mm Above Vanities and Bath. Tiled Shower Walls to ceiling. MGH Standard Range of Tile
Hob Splashback:	MGH Standard Range of Tile Splashback - full width of bench x 750mm high

FLOORING

Tiles:	Tile Flooring to Bathroom & Laundry. Install Included in Contract. MGH Standard Range of Tile
Timber Laminate	Godfrey Hirst 'Fika' Laminate Plank to Kitchen, Dining, Pantry & Entry. MGH Standard Range (Moisture Barrier not Included)
Carpets:	Godfrey Hirst: Windsor or Cable Bay Ranges of Carpet over 95kg Underlay. MGH Traditional Range

LANDSCAPING

Driveway:	Exposed Aggregate 14.16m ²	P.S	\$	2,361.18
Dropdown Kerb:	Street Crossing	P.S	\$	3,277.50
Service Court:	Plain Grey Concrete 6.09m ²	P.S	\$	822.25
Patio(s):	Exposed Aggregate 22.84m ²	P.S	\$	3,808.57
Internal Fence:	1.8m Vertical Dressed Picket Fence with Capping. 140 x 20mm Vertical Pickets. 4 l/m and 2 x Gate	P.S	\$	2,875.00
Fence Paint:	Fence Painting to All Internal and Boundary Fencing - MGH Standard Colours Only	P.S	\$	1,064.90
Boundary Fence:	1.8m Standard Paling Fence (52 l/m) to the Boundaries - 1/2 Share	P.S	\$	4,485.00
Letterbox:	Box Design Urban	P.S	\$	379.99
Clothesline:	Sun King - Double Folding Frame Clothesline	P.S	\$	600.00
Site Levelling:	Clear/Level Site and Add Topsoil 103m ²	P.S	\$	3,269.22
Lawn:	Hydrolawn Supplied 103m ²	P.S	\$	2,369.00
Planting:	Minor Planting Included	P.S	\$	2,000.00

FIXTURES & FITTINGS

Lot 73 Te Mania Development

Date 16/05/2025



Landscaping Total Provisional Sum Cost \$ 27,312.62

Landscaping Total Provisional Sum Cost Including Margin \$ 30,043.88

Signed Client: _____

Signed MGH: _____

Date: _____

VARIATIONS TO CONTRACT

All Client Variations after Signing of the Contract will be Quantified and Priced with a 10% Fixed Margin - Including P.S & P.C Sum Items. Each Order for a Variation shall be Payable at the Next Progress Payment after its Completion

Variations that Require Changes to the Plan will Require Territorial Authority Confirmation. This could Delay or Stop the Project until all Amendments are Approved, and may therefore Effect the Completion Date

PROVISIONAL SUM & PRIME COST SUMS (P.S & P.C SUMS)

All Provisional Sums & Prime Cost Sums are Inclusive of GST. Any Variations Applied to these Sums will be Subject to a 10% Margin